

IRRIGATION AMENDMENTS
See IRRIGATION PLAN, SHEET 4A

REMOVAL OF EXISTING PLAYGROUND EQUIPMENT

- 4 Installation of retaining wall will involve removal of existing equipment. See DETAILING PLAN, SHEET 4B

CONCRETE RETAINING WALL

LANDSCAPE AMENDMENTS REQUIRED
In existing areas disturbed by new construction

PLAYGROUND SURFACE

"Tree" and poured-in-place rubber matting

- 4
- 1
- 4
- 4

SCHOOL-AGE PLAYGROUND EQUIPMENT

Provided by Boise Parks and Recreation, install per manufacturer's instructions, details, and specifications, and in accord to Boise Parks & Recreation specifications, drawings, and details.

CONCRETE SIDEWALK

- 4

CONCRETE PLAZA

- 4

SITE FURNITURE

See specification

- 5

CONCRETE PLAYGROUND CURB

- 4
- 4
- 4
- 4
- 4

PLAYGROUND SURFACE

"Tree" and poured-in-place rubber matting

- 4
- 4
- 4
- 4
- 4

TOT PLAYGROUND EQUIPMENT

Provided by Boise Parks and Recreation, install per manufacturer's instructions, details and specifications, and in accord to Boise Parks and Recreation specifications, drawings, and details.

PROPOSED TREE, TYP.

See PLANTING PLAN, SHEET 4A

CONSTRUCTION AND DEMOLITION NOTES:

- All work shall conform to all City and other governing agencies regulations. Contractor shall obtain all necessary permits, inspections and approvals required for the work.
- Specifications take precedence over drawings and details and should be adhered to in all construction.
- If there are any discrepancies between the actual on-site conditions and those shown on drawings, the Contractor shall notify Boise Parks and Recreation Dept. PRIOR to beginning of construction.
- Contractor shall verify location of all underground utilities and services prior to any digging. Contractor assumes full responsibility for all damage caused by failure to do so.
- All existing structures and existing plant materials as indicated on plan and underground utilities shall be protected from damage during construction.
- Prior to installation of concrete, asphalt, and/or other landscape materials, all paving bases and materials are to be reviewed and approved by Boise Parks and Recreation.
- All debris from demolition and/or clearing shall be hauled from site and disposed of in accord to local codes and regulation, unless otherwise approved by Boise Parks and Recreation Dept.
- See SHEETS 4 & 5 for construction details and contract/project book for specifications.
- Contractor shall provide temporary storage fence for safety and/or line protection as determined or as indicated on job site per Boise Parks and Recreation. Once playground equipment is installed, fence must control access to playground area until surface materials is installed.
- For information about relocation and removal of existing trees, see PLANTING PLAN, SHEET 4A
- For location of irrigation lines, see IRRIGATION PLAN, SHEET 4A

CONSTRUCTION and DEMOLITION LEGEND:

- Existing Fountain
- Trash Receptacle Holder
- Benches
- Base Rock
- Temporary fence for user protection

SCALE: 1"=20'-0"

A. FAIRVIEW NEIGHBORHOOD PARK

TOT LOT AND SCHOOL-AGE PLAYGROUND INSTALLATION

CONSTRUCTION PLAN

24th Street

Barnock Street

Idaho Street

23rd Street

